Wellington Ex Village Sch Dist

FY 2027 FORM 470 #270000811

QUESTION & ANSWER

1. Are there J-hooks in the drop ceilings?
    a. Some ceilings do have J-hooks. Other drop ceilings may not have them.
2. Are there raceways in the classrooms?
    a. Most of the classrooms have raceways.
3. Do any raceways need to be replaced?
    a. The existing raceways should be re-usable.
4. Do you want cabling above CAT6 standard?
    a. Please refer to the Wellington FY27 C2 Pricing Attachment.
5. Are there access points included in this project?
    a. Access points are not part of this project.
6. Do the access point cable runs need to be replaced?
    a. The access point runs can be left as-is.
7. Do you have floor plans?
    a. Please refer to Addendum 3_Wellington_FY27_Drop Locations Map. Drop locations have been marked.
8. Can you provide the number of drops per classroom?
    a. Please refer to Addendum 3_Wellington_FY27_Drop Locations Map. Drop locations have been marked.
9. Demo of the old cables - do they need to be fully pulled out, or can they stay in place?
    a. Removal of old cabling is preferred, but the old cabling can stay in place. Please note that this is a revision to the Wellington FY27 C2 Service Spec.
10. Are there fiber interconnects?
    a. There are no fiber interconnects that are germane to this re-cabling project,
11. Do you have a preference for cable manufacturers?
    a. No preference, though I prefer the snagless style over the molded connectors.
12. Will you be offering any other walkthrough dates, or is it possible to set up a walkthrough to look at the cabling needed?
    a. The walkthrough was optional, and the summary was posted. All questions asked and their answers are included on this addendum. We do not anticipate adding any other walkthrough dates. Please review the FCC Form 470, Service Specifications document, meeting summary, pricing attachment, this Q&A, and the Drop Locations Map for additional information.
13. Are all the new drops replacing existing drops?
    a. Yes. These are 100% replacements of existing drops.
14. Are the drops standard drops for Access Points, classrooms, etc.
    a. They are all classroom drops; the cable runs for the access points are not being replaced

15. Do any locations require the use of a lift to access? If so, is a lift available on-site or should we provide it?
    a. No locations require a lift
16. Is there a preference on cable color?
    a. No preference on cable color
17. Are drawings w/drop location markups available? If not, are just building drawings available?
    a. Please refer to Addendum 3_Wellington_FY27_Drop Locations Map. Drop locations have been marked.