Q&A Responses: AND3-2026-10 E-Rate Form 470 270001838

#	Question	ACSD3 Response
1	Can you provide counts for how many access points will require right angle brackets?	The maps emailed to attendees of the mandatory pre-bid walkthrough identify existing access point locations and mounting types based on a preliminary review by District staff. These maps are provided for estimating purposes and have not been fully verified. Offerors should use the mounting types shown on the maps to estimate bracket quantities. Final bracket requirements will depend on the approved RF design and mounting locations. Please note that if the numbers on the map do not line up with the numbers on the RFP, please assume any missing Access Points will be in the existing location and same model as a classroom AP.
2	Can you provide a drawing showing all data room locations?	Yes - drawings with data room locations has been emailed to those who attended the mandatory pre-bid walkthrough.
3	Can you provide a drawing showing/notating which classrooms have open ceilings?	No. We do not have that information readily available for this RFP, however, you may be able to deduce this type ceiling based on the access point mounting method indicated on the map that has been emailed to all those who attended the mandatory pre-bid walkthrough
4	Can you provide locations of all exterior access points?	Yes - these are indicated on the map emailed to all those who attended the mandatory pre-bid walkthrough.
5	Confirm that, if needed, the school district can and will provide a lift.	Yes, ACSD3 will provide a lift if needed.
6	For the classrooms that do not have a drop ceiling, if the predictive design performed by reseller shows them needing to be moved to the center of the classroom, does the district want to leave them on the wall or propose moving them to the center of the classroom? If moving to the center, do you want the cable exposed or would you like conduit/raceway to be proposed for the installation/move?	Relocation of an access point is acceptable if the predictive RF design demonstrates that its current location would not provide adequate coverage or performance. The Offeror shall identify and justify any proposed relocation, including associated costs, for District approval before installation. Any cabling that cannot be concealed within the building structure shall be enclosed in securely mounted conduit or raceway with a neat, professional appearance.
7	Do you require tunneling to tunnel your wireless data back to your core?	No
8	Do you want to replace the L Brackets and Nema enclosures, or can we re-use them?	Yes, please include a separate line item for the replacement of the L Brackets with a first party hardware bracket or appropriate industry standard equivalent. Existing NEMA enclosures only need to be replaced if the proposed solution hinders performance or functionality.
9	A partner we are working with was unable to attend the walkthrough. Does that disqualify my company's bid?	No, provided your company is the Offeror and was represented for the entire walkthrough. Section III, “Mandatory Walkthrough / Site Review” (page 20) requires attendance but does not require separate attendance by every partner or proposed subcontractor.
10	Do you want to see the optional Marvis and Analytics subscriptions quoted for all access points or just for the AP66 shown in Schedule C section?	The Marvis and Analytics subscriptions should be quoted for all 291 Wireless Access Points shown in Schedule C. An addendum for the RFP adds Marvis and Analytics subscriptions for the 13 Wireless Access Points in Schedule B.

Q&A Responses: AND3-2026-10 E-Rate Form 470 270001838

#	Question	ACSD3 Response
11	Can a representative of a company attend the walkthrough?	Yes, a representative may attend on behalf of the company submitting the bid. Section III, “Mandatory Walkthrough / Site Review” (page 20) requires documented attendance for the entire walkthrough and does not specify that the attendee must be an employee of the Offeror.
12	What is your current networking equipment?	See Q&A - Current Infrastructure.xlsx spreadsheet
13	Can you provide the POE budget for each switch?	See Q&A - Current Infrastructure.xlsx spreadsheet