Jackson County ISD
an Educational Service Agency

Napoleon Community Schools Structured Cabling and Network Cabinet Upgrade
- Addendum 1

Question: Please provide the replacement wall-cabinet dimensions referred to by "size listed below" on page 24.
Answer: It is believed that up to a 33" inch deep cabinet may be needed. There is a unique cabling situation in these locations that prevents certain network equipment from being installed properly. The site visit is an opportunity to see the existing infrastructure. As part of the response, vendors are asked to present the best solution.

Question: What are the IDF1/IDF2 patch-panel port counts to be migrated?
Answer:

- IDF 1 contains approximately five 24 port patch-panels, one 1U fiber optic shelf, three network switches, and a 1U PDU.
- IDF 2 contains approximately five 24 port patch-panels, one 1U fiber optic shelf and three network switches.

Question: What work windows are permitted for the fiber cutover and cabinet swaps: school hours, after hours, or scheduled outage windows?
Answer: Please include pricing for both school hours and after hours, scheduled outage window(s).

Question: Is the existing 12-count WAN cable to be re-housed without re-termination, or should re-termination and testing be included?
Answer: The WAN connection does not terminate in any of these cabinets. The winning bidder is not anticipated to have any interaction with the WAN connection.